CITY OF MILPITAS

Building & Safety Division 455 E. Calaveras Blvd. Milpitas, CA 95035 408-586-3240 www.ci.milpitas.ca.gov



RESIDENTIAL KITCHEN REMODEL

1. PERMIT INFORMATION:

2.

	The remodeling of an existing kitchen requires a Permit. A Combination permit can be obtained that includes building, electrical, mechanical and plumbing permits all in one.			
	A Building Permit may be issued only to a State of California Licensed Contractor or the Homeowner.			
	If the work is performed by the Homeowner personally or by his/her workers, and an inspection indicates the work cannot be completed satisfactorily, then a licensed contractor must perform the work.			
	If the Homeowner hires workers, State Law requires the Homeowner to obtain Worker's Compensation Insurance. Proof of this insurance is required prior to inspection.			
<u>IN</u>	STALLATION REQUIREMENTS:			
	Building Codes: All work must comply with the 2010 California Building Code (CBC), 2010 California Residential Code (CRC), 2010 California Mechanical Code (CMC), 2010 California Electrical Code (CEC), 2010 California Plumbing Code (CPC), 2010 California Energy Code based upon 2008 Building Energy Efficiency Standards (CEnC) and 2011 Milpitas Municipal Code (MMC).			
	On-line permits can only be obtained for kitchen remodels that do not include any modifications to the existing wall and/or ceiling framing.			
	If any changes will be made to the existing framing, or if any appliances will be relocated, drawings must be submitted and approved and the permit obtained in person from the Permit Center, Building & Safety Department, 455 E. Calaveras Blvd. The drawings required may include:			
	 Floor plan: Indicate walls, windows (size and type), and door sizes. Show adjoining rooms and label the use of each room. Show location of all cabinets (upper and lower) and plumbing fixtures and show their dimensions. Ceiling plan: If needed to show ceiling heights, electrical and mechanical installed in the ceiling. Structural: If any walls are being removed or relocated, show existing framing that shows the walls were not bearing, or if they were, how the support is being replaced. Electrical, mechanical & plumbing: Show electrical receptacles, electrical fixtures with switching, and ventilation. May be included on the floor plan. Details and Notes: Provide all details and notes required to explain the work. All drawings must be signed by the person preparing them. 			
	In single family residences and multi-family (townhomes, condominiums, and apartments), installation of smoke detectors, carbon dioxide alarms and spark arrestors on all chimneys is required prior to the final inspection as follows:			

- Smoke Alarms: When the value of the work exceeds \$1,000, smoke alarms approved and listed by the State Fire Marshal must be installed if they do not already exist in each sleeping room, outside each separate sleeping area in the immediate vicinity of the bedrooms, and on each additional story of the dwelling. In existing buildings, alarms may be solely battery operated where alterations or repairs do not result in the removal of interior walls or ceiling finishes exposing the structure, unless there is an attic, crawl space or basement available which could provide access for building wiring without the removal of interior finishes. Where more than one smoke alarm is required to be installed, the alarms shall be interconnected in such a manner that the activation of one alarm will activate all of the alarms in the individual unit, except where alterations or repairs do not result in the removal of interior wall or ceiling finishes exposing the structure, unless there is an attic, crawl space or basement available which could provide access for interconnection without the removal of interior finishes. The alarm shall be clearly audible in all bedrooms over background noise levels with all intervening doors closed. Refer to CRC Section R314 and the "Smoke Alarms" handout for more additional information.
- Carbon Monoxide Alarms: When the value of the work exceeds \$1,000, an approved and listed carbon monoxide alarm shall be installed if they do not already exist in existing dwellings or sleeping units that have attached garages or fuel-burning appliances as follows: outside each separate dwelling unit sleeping area in the immediate vicinity of bedrooms and on every level of dwelling unit. In existing dwelling units a carbon monoxide alarm is permitted to be solely battery operated where repairs or alterations do not result in the removal of wall and ceiling finishes or there is no access by means of attic, basement or crawl space. Where more than one carbon monoxide alarm is required to be installed, the alarms shall be interconnected in a manner that activation of one alarm shall activate all of the alarms in the individual unit, except where repairs do not result in the removal of wall and ceiling finishes, there is no access by means of attic, basement or crawl space, and no previous method for interconnection existed. See CRC Section R315 for additional information.
- **Spark arrester:** When the value of the work exceeds \$1,000, a spark arrester must be installed on fireplace chimneys if one does not already exist per MMC Section II-3-2.06. Spark arresters shall be constructed in conformance with CRC Section 1003.9.1.

3. ROOM REQUIREMENTS:

٠.	I	ONI REQUIREMENTS.	
		Ceiling height shall not be less than 7'-0" in kitchen per CRC Section R305.1 .	
		A self-closing, tight fitting, solid-wood door 1-3/8" thick or a 20-minute fire-rated door is required between a kitchen and the garage per CRC Section R302.5.1.	
1.	 <u>ELECTRICAL REQUIREMENTS</u> – Installation of any new or replacement of any existing electrical shall comp with the following. NOTE: All kitchen remodels must include upgrading the existing receptacles to have GF protection if not already existing. 		
		If new circuits or additional loads are being added, including adding new outlets, and the service is less than 100 amps, the service panel must be upgraded to a minimum 100 amps (CEC 230.79(C).	
		A receptacle outlet shall be installed at each wall countertop space that is 12 inches or wider. Receptacle outlets shall be installed so that no point along the wall line is more than 24 inches measured horizontally from a receptacle outlet in that space. per CEC Section 210.52(C)(1).	
		Receptacle outlets shall be located above, but not more than 20 inches above the countertop and not in a face-up position on the countertop. Receptacle outlets rendered not readily accessible by appliances fastened in place shall not be considered as these required outlets per CEC Section 210.52(C)(5).	

Building and Safety Department Bathroom Remodel

5.

6.


	Outlet boxes shall be installed so the front edge of the box, plaster ring, extension ring, or listed extender will not be set back of the finished surface more than ¹ / ₄ ". Installation of new counter backsplash or other wall finishes may require the extension of existing boxes. (CEC 314.20)
	At least one receptacle is required at island and peninsular countertops with a long dimension of at least 24 inches and a short dimension of at least 12 inches per CEC Section 210.52(C)(2) and (3).
	CEC Section 210.52(B) requires two or more 20-ampere small appliance branch circuits for all receptacle outlets for the small appliance loads (including refrigeration equipment) in the kitchen, dining room, pantry, breakfast room, electric clock receptacle, and electric loads associated with gas fired appliances; but these circuits are to have no other outlets. Provide separate circuits for the garbage disposal and the dishwasher.
	Receptacles shall be protected with GFCI(s) per CEC Section 210.8(A)(6). Refrigeration equipment is exempt from the GFCI requirements. 210.52(B1 exception #2 shall be permitted to be supplied from individual branch circuit.
	Branch circuit conductors supplying ranges, ovens and other cooking appliances shall have an ampacity rating of not less than the maximum load served. For ranges $8\frac{3}{4}$ kW or more rating, the minimum branch-circuit rating shall be 40 amperes per CEC Section 210.19(A)(3). A minimum 40-ampere rating would be No. 8 type TW copper or No. 6 Type TW aluminum.
EN	IERGY REQUIREMENTS:
	All lighting must comply with all applicable mandatory measures of the California Energy Code. Refer to the attached form MF-1R for a list of the mandatory requirements.
	If adding or replacing lighting in the kitchen, a minimum of 50% of the total rated lighting wattage (based on the maximum allowed for each fixture) shall be high efficacy fixtures (e.g. fluorescent) switched separately from any low efficacy lighting.
	Permanent lighting internal to cabinets shall not use more than 20 watts of power per linear foot of illuminated cabinet.
	Recessed lighting in insulated ceilings must be rated for direct insulation contact (IC), certified as airtight construction (AT), and must have a sealed gasket or caulking between the housing and ceiling to prevent the flow of heated or cooled air out of the living areas and into the ceiling cavity (CEnC 150(k)12).
	Luminaries installed to meet the minimum lumens per watt requirement (high efficacy) shall not contain medium base incandescent lamp sockets.\
	Title 24 Energy Compliance Reports: The following forms must be filled out and attached to the permit prior to inspection:
	 Mandatory Measures form MF-1R. Installation Certificate CF-6R-LTG-01.
PL	UMBING REQUIREMENTS:
	On the discharge side of the dishwasher provide a listed air gap fitting. Listed air gaps shall be installed with the flood level (FL) marking at or above the flood level of the sink or drain board whichever is higher per CPC Section 807.4.

- New gas piping must be installed back to the meter or calculations must be provided to show the existing piping is adequately sized.
- ☐ It is the responsibility of the installer to verify that the new or existing gas supply is correctly sized before installation. Refer to the separate handout "Gas Piping" for additional information.
- □ Listed flexible gas connectors in compliance with CSAZ21.24, Standard for Connectors for Gas Appliances. The connector shall be used in accordance with the terms of their listing that are completely in the same room as the appliance. [NFPA 54:9.6.1(3)] Connectors must be located completely in the same room as the appliance. The listed metal connector for a gas range or oven installation shall be sized to appliance demand (established by manufacturer) and shall be a maximum of 6 feet long. (CPC Section 1212.0)
- ☐ An approved Excess Flow Gas Shut-off Device (non-motion sensitive) shall be installed at the gas fuel appliance outlet when replacing any existing gas fuel appliance or when installing any new gas fuel appliance. The Excess Flow Device shall be installed between the shutoff valve and the connector. (MMC II-170-2.00)






Close up view of an excess flow device:



An approved Seismic Gas Shut-off Device (motion sensitive) *or* an approved Excess Flow Gas Shut-off Device (non-motion sensitive) shall be installed downstream of the gas utility meter (after PG&E service tee), but upstream of any appliances, where the gas line serves any new building (commercial, industrial or residential) or when providing alteration or addition to the existing gas fuel line. (MMC II-170-2.00)



"California Valve"







- Automatic Gas Shut-off Devices shall be installed by a contractor licensed in the appropriate classification by the State of California and in accordance with the manufacturer's instructions.
- ☐ Seismic Gas Shut-off Devices (motion sensitive) must be mounted rigidly to the exterior of the building or structure containing the fuel gas piping. This requirement need not apply if the Building and Safety Department determines that the Seismic Gas Shut-off Device (motion sensitive) has been tested and listed for an alternate method of installation.
- ☐ Both Seismic Gas Shut-off Devices (motion sensitive) and Excess Flow Gas Shut-off Devices (non-motion sensitive) must be certified by the Office of State Architect and be listed by an approved listing and testing agency such as IAS, IAPMO, UL or the Office of State Architect.
- □ Both Seismic Gas Shut-off Devices (motion sensitive) and Excess Flow Gas Shut-off Devices (non-motion sensitive) must have a thirty (30) year warranty which warrants that the valve or device is free from defects and will continue to operate properly for thirty (30) years from the date of installation.
- ☐ Where Automatic Gas Shut-off Devices are installed voluntarily or as required by code, they shall be maintained for the life of the building or structure or be replaced with a valve or device complying with the requirements of this section.

7.	MECHANICAL	REQUIREN	MENTS:
----	-------------------	----------	---------------

CMC 916.(B): Vertical Clearance Above Cooking Top. Household cooking appliances shall have a vertical	
clearance above the cooking top of not less than thirty (30) inches to combustible material or metal cabinets.	A
minimum clearance of twenty-four (24) inches is permitted when one of the following is installed:	

- The underside of the combustible material or metal cabinet above the cooking top is protected with not less than one-fourth of inch insulating millboard covered with sheet metal not less than 0.0122 inch thick.
- A metal ventilating hood of sheet metal not less than 0.0122 inch thick is installed above the cooking top with a clearance of not less than one fourth of inch between the hood and the underside of the combustible material or metal cabinet, and the hood is at least as wide as the appliance and is centered over the appliance.
- A listed cooking appliance or microwave oven is installed over a listed cooking appliance and will conform to the terms of the upper appliance's listing and the manufacturer's instructions. [NFPA 54: 10.15.1.2]


Kitchen hood ventilation can be met with either a ducted range hood, a ceiling or wall mounted exhaust fan, or ducted ventilation system that provides at least 5 air changes of the kitchen volume per hour. A minimum intermittent ventilation airflow rate of 100 cfm and a maximum of 3.0 sone rate are required for kitchen exhaust fan per CEnC.Sec.150(o) & ASHREA 62.2.
Microwave must be listed for installation over range.
Exhaust ducts shall terminate outside the building and shall be equipped with a back-draft damper per CMC Section 504.1. Ducts shall terminate 3 feet from property line and 3 feet from openings into building.

8. <u>INSPECTIONS</u>:

A minimum of two inspections is required for kitchen remodels. A rough electrical inspection should be scheduled after the electrical boxes are installed and before any devices are connected. Any other structural, mechanical, or plumbing alterations should also be scheduled for a rough inspection. Additional inspections may be needed based on extent of the project. The final inspection should be scheduled after all the work is completed. Review with your inspector during the first inspection the requirements for your project. For each inspection, the Permit Card with the Energy Compliance Report forms completely filled and out attached, and the Approved Job Copy of the Drawings (if any) must be presented to the inspector. Permits expire 180 days after the last passed inspection.

9. **QUESTIONS**:

	If you have any	questions regarding	your project cont	tact the Building	& Safety De	enartment at (40	08) 586-3240
_	II you have any	questions regarding	your project com	iact the Dunuing (cc saicty De	parunom at (+c	101 JUU-J _T U.




SAMPLE FLOOR PLAN

REQUIRED CIRCUITS

(2)	SMALL APPLIANCES BRANCH CIRCUIT
(1)	LIGHTING
(1)	GARBAGE DISPOSAL
(D)	TRASH COMPACTOR
(D)	RANGE
(1)	OVEN
(1)	DISHWASHER
(1)	WARMER DRAWER
(1)	INSTANT HOT
(1)	MICROWAVE
(D)	HOOD
(1)	REFRIGERATOR
	(IF BUILT IN)

ABBREVIATION

REF	REFRIGERATOR
CKTP.	COOK TOP
6	SINK
DW	DISHWASHER
GD	GARBAGE DISPOSAL
MW	MICROWAVE







ABBREVIATION

REFRIGERATOR
соок тор
SINK


SAMPLE LIGHTING FLOOR PLAN



SAMPLE RECEPTACLES ELECTRICAL FLOOR PLAN



SAMPLE RECEPTACLES ELECTRICAL FLOOR PLAN



NOTE "A"

- □ CMC 916.(B): Vertical Clearance Above Cooking Top. Household cooking appliances shall have a vertical clearance above the cooking top of not less than thirty (30) inches to combustible material or metal cabinets. A minimum clearance of twenty-four (24) inches is permitted when one of the following is installed:
 - The underside of the combustible material or metal cabinet above the cooking top is protected with not less than one-fourth of inch insulating millboard covered with sheet metal not less than 0.0122 inch thick.
 - A metal ventilating hood of sheet metal not less than 0.0122 inch thick is installed above the cooking top with
 a clearance of not less than one fourth of inch between the hood and the underside of the combustible
 material or metal cabinet, and the hood is at least as wide as the appliance and is centered over the appliance.
 - A listed cooking appliance or microwave oven is installed over a listed cooking appliance and will conform to the terms of the upper appliance's listing and the manufacturer's instructions. [NFPA 54: 10.15.1.2]

REY.	DATE	BY:	SCALE:	City of Milaitos	GILLEE
Ü	01/2011	ВK	N.T.S	City of Milpitas	SHEET
			DATE: AUG. 2006	Building & Safety Division	1
			DRAWN BY: BK.	RESIDENTIAL COOK-TOP RANGE	OF 1 SHEETS

Mandatory Measures Summary	Lighting Only	MF-1R	
Residential		2.25.	
Site Address:	Enforcement Agency: City of Milpitas	Date:	

Residential Lighting Measures:

- §150(k)1: High efficacy luminaires or LED Light Engine with Integral Heat Sink has an efficacy that is no lower than the efficacies contained in Table 150-C and is not a low efficacy luminaire as specified by §150(k)2.
- §150(k)3: The wattage of permanently installed luminaires shall be determined as specified by §130(d).
- §150(k)4: Ballasts for fluorescent lamps rated 13 Watts or greater shall be electronic and shall have an output frequency no less than 20 kHz.
- §150(k)5: Permanently installed night lights and night lights integral to a permanently installed luminaire or exhaust fan shall contain only high efficacy lamps meeting the minimum efficacies contained in Table 150-C and shall not contain a line-voltage socket or line-voltage lamp holder; OR shall be rated to consume no more than five watts of power as determined by §130(d), and shall not contain a medium screw-base socket.
- §150(k)6: Lighting integral to exhaust fans, in rooms other than kitchens, shall meet the applicable requirements of §150(k).
- §150(k)7: All switching devices and controls shall meet the requirements of §150(k)7.
- §150(k)8: A minimum of 50 percent of the total rated wattage of permanently installed lighting in kitchens shall be high efficacy.
- EXCEPTION: Up to 50 watts for dwelling units less than or equal to 2,500 ft² or 100 watts for dwelling units larger than 2,500 ft² may be exempt from the 50% high efficacy requirement when: all low efficacy luminaires in the kitchen are controlled by a manual on occupant sensor, dimmer, energy management system (EMCS), or a multi-scene programmable control system; and all permanently installed luminaries in garages, laundry rooms, closets greater than 70 square feet, and utility rooms are high efficacy and controlled by a manual-on occupant sensor.
- §150(k)9: Permanently installed lighting that is internal to cabinets shall use no more than 20 watts of power per linear foot of illuminated cabinet.
- §150(k)10: Permanently installed luminaires in bathrooms, attached and detached garages, laundry rooms, closets and utility rooms shall be high efficacy.
 - EXCEPTION 1: Permanently installed low efficacy luminaires shall be allowed provided that they are controlled by a manual-on occupant sensor certified to comply with the applicable requirements of §119.
 - EXCEPTION 2: Permanently installed low efficacy luminaires in closets less than 70 square feet are not required to be controlled by a manual-on occupant sensor.
- §150(k)11: Permanently installed luminaires located in rooms or areas other than in kitchens, bathrooms, garages, laundry rooms, closets, and utility rooms shall be high efficacy luimnaires.
 - EXCEPTION 1: Permanently installed low efficacy luminaires shall be allowed provided they are controlled by either a dimmer switch that complies with the applicable requirements of §119, or by a manual-on occupant sensor that complies with the applicable requirements of §119.
 - EXCEPTION 2: Lighting in detached storage building less than 1000 square feet located on a residential site is not required to comply with §150(k)11.
- \$150(k)12: Luminaires recessed into insulated ceilings shall be listed for zero clearance insulation contact (IC) by Underwriters Laboratories or other nationally recognized testing/rating laboratory; and have a label that certifies the luminaire is airtight with air leakage less then 2.0 CFM at 75 Pascals when tested in accordance with ASTM E283; and be sealed with a gasket or caulk between the luminaire housing and ceiling.
- §150(k)13: Luminaires providing outdoor lighting, including lighting for private patios in low-rise residential buildings with four or more dwelling units, entrances, balconies, and porches, which are permanently mounted to a residential building or to other buildings on the same lot shall be high efficacy.
 - EXCEPTION 1: Permanently installed outdoor low efficacy luminaires shall be allowed provided that they are controlled by a manual on/off switch, a motion sensor not having an override or bypass switch that disables the motion sensor, and one of the following controls: a photocontrol not having an override or bypass switch that disables the photocontrol; OR an astronomical time clock not having an override or bypass switch that disables the astronomical time clock; OR an energy management control system (EMCS) not having an override or bypass switch that allows the luminaire to be always on
 - EXCEPTION 2: Outdoor luminaires used to comply with Exception1 to §150(k)13 may be controlled by a temporary override switch which bypasses the motion sensing function provided that the motion sensor is automatically reactivated within six hours
 - EXCEPTION 3: Permanently installed luminaires in or around swimming pool, water features, or other location subject to Article 680 of the California Electric Code need not be high efficacy luminaires.
- §150(k)14: Internally illuminated address signs shall comply with Section 148; OR not contain a screw-base socket, and consume no more than five watts of power as determined according to §130(d).
- \$150(k)15: Lighting for parking lots and carports with a total of for 8 or more vehicles per site shall comply with the applicable requirements in Sections 130, 132, 134, and 147. Lighting for parking garages for 8 or more vehicles shall comply with the applicable requirements of Sections 130, 131, 134, and 146
- §150(k)16: Permanently installed lighting in the enclosed, non-dwelling spaces of low-rise residential buildings with four or more dwelling units shall be high efficacy luminaires.
 - EXCEPTION: Permanently installed low efficacy luminaires shall be allowed provided that they are controlled by an occupant sensor(s) certified to comply with the applicable requirements of §119.

INSTALLATION (CERTIFICATE								CF-6R-LTG-01
Residential Lightin	g								(Page 1 of 3)
Site Address:				Enforce	men	t Agency:	1	Permit	Number:
1. Kitchen Lighting									
Does project include kitc									
☐ Yes, complete section☐ Yes §150	1 \square No, go on to so $(k)3$: The wattage of p		ad lı	minaires (ligi	ntina	fixtures) 1	nas haan datarm	inad ac	enacified by \$120(d)
	(k)3: In the kitchen, a								
installed, and where the									
☐ Yes ☐ NA Watt	age has been calculate	d as 180 watts of l	ow e	efficacy lighting	ng pe	r blank el	ectrical box.		•
§150(k)8 Kitchen I	0 0	nply with eith	er n	nethod (a),	(b),	or (c) b	elow:		
(a) All high effi	cacy luminaires								
☐ Yes, complies because	e only high efficacy lu	uminaires have bee	n in	stalled in the l	citche	en.			
☐ No, complies with me	ethod (b) or (c).								
(b) ≥ 50% watts	s used by high eff	icacy luminair	es						
☐ Yes, complies becaus	e at least 50% of the i	nstalled watts are f	rom	permanently	instal	lled high e	fficacy luminai	res	
as demonstrated in the ta	ble below: Total $A \ge 7$			•					
☐ No, complies with me	ethod (a) or (c).								
Eill and the Callernia a tale	1. :C	:41411 (1-)	(a)						
Fill out the following tab	ie ii compiying with e	itner method (b) of	r (c).						
Table (b)	Efficacy				l	I			
I uminaira Tuma	Efficacy	Watta		Overtity	_	High E	fficary Watta	22	Low Efficient Wette
Luminaire Type	High Low	Watts	X	Quantity	=	High E	fficacy Watts	or	Low Efficacy Watts
			X		_			or	
			X		=			or	
	+		+		=			25	
			X		_			or	
			X		=			or	
			+		=				
			X					or	
Complies with method	$d(b)$ if $A \ge B$			Total:	A:			\geq	B:
(c) Additional Kitchen Low Efficacy Lighting						·			
. ,		• 0 0							
☐ Yes, complies becaus									
and as demonstrated in ta		the table in (c) (be	elow) that (A + C) ≥ E	3			
☐ No, complies with me	etnod (a) or (b).								
A dditio	nal kitahan law a	ffice ev lighting	- ic	availahla a	n lv	if all af	tha fallawin	G 040	two
☐ Yes. All low efficacy	nal kitchen low e					II all oi	the lonowin	gare	true:
Dimmer energy manager						ntrol syste	em		
								rooms	are high efficacy
☐ Yes. Permanently installed luminaires in garages laundry rooms closets greater than 70 square feet and utility rooms are high efficacy luminaires AND are controlled by a vacancy sensor.									
Table (c)									
		Use 50 W for							
			or dv		elling units $> 2,500 \text{ ft}^2$ A				Yes/No?
A	В С			С			A + C	,	Is $(A+C) \ge B$?
2. Lighting Interna	l to Cabinets					ļ			
Does project includes lig		ets?							
☐ Yes_complete section									

 \square Yes, §150(k)9: Permanently installed lighting internal to cabinets uses ≤ 20 watts of power per linear foot of illuminated cabinet.

INSTALLATION CERTIFICATE CF-6R-LTG-01							
Residential Li			(Page 2 of 3)				
Site Address:	gnung	Enforcement Agency:	Permit Number:				
Site Huuress.		Emorement rigency.	Termit (valider)				
	3. Installed Devices and Components Have Been Certified to the Energy Commission Does the project include any of the devices or components listed below? ☐ Yes, complete section 3 ☐ No, go on to section 4						
☐ Yes	nertiale any of the devices of components fished below:	2 res, complete section 5	, go on to section 4				
	7(F): Any of the following devices and components wh						
	pplicable provisions of §119: All LED lighting systems						
vacancy sensors (a	vacancy sensors (automatic off/manual on occupant sensors), dimmers, track lighting integral current limiters, and outdoor motion sensors.						
4. Lighting Controls Complete section 4							
☐ Yes ☐ NA							
☐ Yes ☐ NA	·						
☐ Yes ☐ NA §150(k)7C: All permanently installed luminaires are switched with readily accessible controls that permit the luminaires to be manually switched on and off.							
☐ Yes ☐ NA	§150(k)7D: All lighting controls have been installed	in accordance with the manufacturer'	s instructions.				
☐ Yes ☐ NA	§150(k)7E: All lighting circuits that are controlled by						
	installed to comply with §150(k), no controls bypass	the dimmer or vacancy sensor function	ons.				
	(Lighting Fixtures)						
Does the project include the installation of any luminaires (indoor or outdoor)?							
	section 5 \(\subseteq \text{No, go on to section 6} \)						
	acy luminaire classification has been determined accordate determined according to §150(k)2.						
☐ Yes ☐ NA	§150(k)4: Fluorescent lamps rated 13 watts or greate kHz.	r have an electronic ballasts having a	n output frequency no less than 20				
☐ Yes ☐ NA	§150(k)5: Permanently installed night lights, and nig						
	contain only high efficacy lamps meeting the minimu						
	socket or line voltage lamp holder, OR the night light a medium screw-base socket.	is rated to consume no more than 3	watts of power and does not contain				
☐ Yes ☐ NA	§150(k)6: Lighting integral to exhaust fans, in rooms	s other than kitchens, meet the applica	able requirements of \$150(k).				
☐ Yes ☐ NA	Any electrical box finished with a blank cover or who	* * * * * * * * * * * * * * * * * * * *					
_ 103 _ 1111	box can be used for a luminaire or a surface mounted						
	with §150(k).						
Does the project include any luminaires that are recessed into insulated ceilings?							
	the rest of section 5 No, go on to section 6						
	2: Luminaires that are recessed into insulated ceilings						
☐ Yes, are listed, as defined in §101, for zero clearance insulation contact (IC) by UL or other nationally recognized testing/rating laboratory, and							
	have labels that certify the luminaires are airtight with	air leakage less than 2.0 CFM at 75 I	Pascals when tested in accordance				
	ASTM E283 (Exhaust fan housings are not required to						
	are sealed with a gasket or caulk between luminaire ho anditioned spaces have been sealed with a gasket or cau						
	allows ballast maintenance and replacement to be read iring the cutting of holes in the ceiling.	ily accessible to building occupants f	rom below the ceiling without				
6. Indoor Lighting (any indoor room that is not a kitchen) Does the project include permanently installed luminaires in any room that is not a kitchen?							
☐ Yes, complete		at is not a kitchen?					
☐ Yes ☐ NA	\$150(k)10: Permanently installed luminaires in bathr	ooms garages laundry rooms closet	$s > 70 \text{ ft}^2$ and utility rooms are high				
	efficacy luminaires OR are controlled by a vacancy s						
☐ Yes ☐ NA	§150(k)11: Permanently installed luminaires located i						
	rooms, closets, and utility rooms are high efficacy lun	minaires, OR are controlled by a dimi	mer switch OR are controlled by				
	a vacancy sensor.						

INSTALLAT		TIFICATE		CF-6R-LTG-01
Residential L	ighting			(Page 3 of 3
Site Address:			Enforcement Agency:	Permit Number:
			·	
7. Outdoor L	ighting	ermanently installed outdoor ligh	ting?	
		No, go on to section 8	ung:	
□ Yes □ NA	§150(k)13: with four or building or motion sens	Luminaires providing outdoor lig r more dwelling units, entrances, b to other buildings on the same lot for not having an override or bypa control methods:	hting, including outdoor lighting for private palconies, and porches, and which are permare high efficacy luminaires OR are controls switch that disables the motion sensor,	nanently mounted to a residential olled by a manual on/off switch, plus a plus one of the following three
	8	-	have an override or bypass switch that dis-	-
	1	 An astronomical time clock r or 	not having an override or bypass switch that	at disables the astronomical time clock;
		c. Energy management control luminaire to be always on.	s systems (EMCS) not having an override	or bypass switch that allows the
□ Yes □ NA	switch which	ch temporarily bypasses the motio	res used to comply with Exception 1 to \$15 n sensing function, and the motion sensor control, astronomical time clock, or EMCS	is automatically reactivated within six
□ Yes □ NA			d luminaires in or around swimming pools ic Code which do not need to be high effic	
☐ Yes ☐ NA	§150(k)14: more than 5	Internally illuminated address sign watts of power as determined according to the state of the s	gns comply with §148, OR do not contain a cording to §130(d).	a screw-base socket and consume no
□ Yes □ NA	§130,132, 1		oorts with a total of 8 or more vehicles per g garages for 8 or more vehicles comply w must be submitted	
		v-rise residential buildings stallation of any luminaires in co	s mmon areas of low-rise residential building	gs?
		No, go on to section 9	-	
			sed, non-dwelling spaces of low-rise reside controlled by occupant sensor(s) certified	
DECLARATION • I certify under	_		e of California, the information provided or	n this form is true and correct
• I am eligible	under Divisio	• •	ns Code to accept responsibility for constr	
I certify that	the installed f	eatures, materials, components, or	r manufactured devices identified on this c s consistent with the plans and specificatio	
requirementsI will ensure permit(s) iss	for the install that a comp ued for the b of this Install	lation. I certify that the requirement leted, signed copy of this Installated uilding, and made available to the	form approved by the enforcement agency ents detailed on the CF-1R that apply to the ation Certificate shall be posted, or mad the enforcement agency for all applicabl be included with the documentation the	e installation have been met. le available with the building e inspections. I understand that a
		ubcontractor or General Contract	or or Builder/Owner)	

Responsible Person's Signature:

Position With Company (Title):

Date Signed:

Responsible Person's Name:

CSLB License: